## Space Launch Systems

October 19, 1988

A. C. Morrissey

MARTIN MARIETTA

# Operational Titan Launch Vehicles

Air Force launch vehicle for West Coast launches of small spacecraft.

Contract for refurbishment of fourteenTitan IIs through 1995.

Low earth polar orbit

(100 nm x 100 nm)

Maximum payload

9.3 ft dia x 30 ft long

4.200 lbs

envelope

Martin Marietta launch vehicle for East Coast launches of commercial and government spacecraft.

Three DOD Titan 34Ds in inventory. Final launch in 1989.

First commercial launch in 1989.

Geosynchronous transfer (Transtage, IUS, TOS) and low earth orbit missions (PAM-D. PAM-DII, SCOTS, integral)

Low earth orbit (80 nm x 140 nm) performance capability 31,600 lbs


Maximum payload envelope 12 ft dia x 47 ft long

Air Force launch vehicle for East and West Coast launches of large spacecraft.


Contract for 23 Titan IVs through 1993.

Centaur, IUS, and No Upper Stage missions


payload envelope - 61.7 ft







TITAN II



MARTIN MARIETTA

TITAN IV

# Titan IV

### Titan IV Overview

#### Air Force Space Division Customer: Build and launch twenty-three vehicles. Program : Initial Launch Capability: Inertial Upper Stage - 4th quarter 1988 No Upper Stage (CCAFS) - 1st quarter 1989 No Upper Stage (Vandenberg) - 1st quarter 1990 Centaur - 2nd quarter 1990 February 28, 1985 Authority to Proceed: Martin Marletta Airframe Prime Contractor: Vehicle Integration Payload Integration Launch Operations Principal Subcontractors: General Dynamics Centaur Upper Stage McDonnell Douglas Payload Fairings United Technologies Solid Rocket Motors Hercules Solid Rocket Motor Upgrade Aerojet TechSystems • Liquid Rocket Engines **Delco Electronics** Guidance SCI Instrumentation Cincinnati Electronics · Command Receivers TITAN IV Analex Centaur Consultant

Inertial Upper Stage

Associate Contractor:

Boeing

## Titan IV Program Summary

#### **Program Status**

- 23-vehicle program baseline; additional vehicle follow-on ATP early 1989
- Five configurations, two upper stages, and launch capability from both coasts

#### Core Vehicle

- · First flight vehicle on the launch pad
- Second flight vehicle delivered to Cape Canaveral

#### Liquid Rocket Engines

- · First five systems complete
- · Two systems shipped to Cape Canaveral

#### Solid Rocket Motors

- Reviews and testing complete
- · First flight motors stacked and mated to core

#### Solid Rocket Motor Upgrade

- First full-scale case winding complete
- Preliminary Design Review scheduled October 1988

#### Payload Fairing

- · Two units delivered to Cape Canaveral
- First flight unit in launch site processing

#### Centaur

- · Tank design complete, test tank in major weld
- Qualification/design evaluation tests in progress

